



### Notice Inviting Quotations (NIQ)

National Institute of Design (NID) invites sealed quotations from the reputed and experienced vendor / agencies for "Supply and laying Telephone Cable, Cable jointing, and DB Fixing works at NID Ahmedabad campus" as per enclosed drawings, schedule, terms & conditions.

The quotations shall be received in the Office of the Chief Administrative Officer, NID, Paldi, Ahmedabad.

The last date of submission of quotations: upto 5.00 pm on upto 15.02.2023

Name of Work :	Supply and laying Telephone Cable, Cable jointing, and DB Fixing works at NID Ahmedabad campus
Estimated cost of work :	Rs 1,65,000/- plus GST
Period of contract :	30 days
Date & Time of opening of quotations :	16.02.2023 at 11.00am at NID Paldi, Ahmedabad

#### Terms & conditions:

1. The rates are to be quoted exclusive of GST and inclusive of all labour, material, tools, plants, carriages etc. If the tax bifurcation is not done, the quoted amount will be considered inclusive of all taxes, duties, other charges etc.
2. **The bidder is advised to visit the site before submitting the quotation at his own cost, and examine it and its surroundings to collect all information that he consider necessary for proper execution of the work. Experience certificates should be submitted by bidder.**
3. **Experience certificate of similar works should be submitted by bidder as under :**
  - Three similar works each value not less than Rs 0.66 Lakhs  
OR
  - Two similar works each value not less than Rs 0.99 Lakhs  
OR
  - One similar works each value not less than Rs 1.32 Lakhs
4. Guarantee Period / Defect liability period: The defect liability period will be of 6 months from the date of completion of work / handing over to NID whichever is later.
5. Scope of work :
  - Supply & laying Telephone Cable, Cable jointing, and DB Fixing works
  - For fixing of Electrical fixtures etc. necessary cutting facility will be provided by vendor as per NID's requirement.
  - The work should be in perfect line & level and to match as per existing steps, slope & levels.
6. Horizontal direction drilling/boring without damage of surface road using Auger Machine. The bore shall be required dia. including insertion of different dia DWC pipe/ GI pipes coupling etc.

7. The payment would be released against on actual measurement of work done and submission of invoice duly checked, verified and certified for payment by internal technical team, Executive Engineer and HOD of NID.
8. EMD : Rs 5,000/- by Demand Draft/ Banker's Cheque/ Pay Order drawn on a Nationalized /Scheduled Bank payable at Ahmedabad in favour of the "National Institute of Design" with the submission of bid.
9. Performance Security : 5% of total contract value including taxes ( including submitted EMD ) to be submitted after issue of work order within 7 days' time period.
10. Security Deposit: 5% (Five ) percentage of gross value of running bill / final bill will be deducted.
11. Performance Security & Security Deposit will be released after satisfactory completion of defect liability period of 90 days.
12. The work should be commenced within a week time from the date of issue of Work Order & completed by 30 days from the issue of work order. Electricity & water will be supplied at one point free of cost.
13. The quoted items rates will be valid for one year for minor repairing and maintenance works within NID Ahmedabad campus with the same rates, terms & conditions.
14. NID reserves the right to reject any or all the Quotations, in part or full, without assigning reason thereof
15. NID reserves the right increase/decrease the quantities upto 25% as per requirement of NID.
16. The successful bidder will have to complete the listed work(s) with the complete satisfaction within 30days. Penalty @ 0.5 % of quoted value per week will be deducted for delay of the work beyond stipulated completion date.

Chief Administrative Officer  
NID

### Schedule of Quantity

**Name of work:** Supply and laying Telephone Cable, Cable jointing, and DB Fixing works at NID Ahmedabad campus.

NIQ No. NID/NIQ/07/22-23

Sr. No	Description	Quantity	Unit	Rate(Rs.)	Amount (Rs.)
1	Supply & installation ( including excavation / Horizontal direction drilling/boring without damage of surface road using Auger Machine / refilling & levelling) of Solid Polythene Insulation copper conductor Jelly Filled core wrapped polyester moisture Barrier Polyal screened Black Polythene Inner Sheath Black 03c Polythene outer sheathed under ground Armoured telephone <b>cables 0.50mm</b> Make FINOLEX/ Polycab <b>50 PAIR JFA</b> ( Quoted rates are inclusive of laying & clamping charges, termination charges etc including all)	200	Meter		
2	Supply & installation ( including excavation / Horizontal direction drilling/boring without damage of surface road using Auger Machine / refilling & levelling ) of Solid Polythene Insulation copper conductor Jelly Filled core wrapped polyester moisture Barrier Polyal screened Black Polythene Inner Sheath Black 03c Polythene outer sheathed under ground Armoured telephone <b>cables 0.50mm</b> Make FINOLEX/ Polycab <b>20 PAIR JFA</b> ( Quoted rates are inclusive of laying & clamping charges, termination charges etc including all)	125	Meter		
3	Supply & installation ( including excavation / Horizontal direction drilling/boring without damage of surface road using Auger Machine / refilling & levelling )of Solid Polythene Insulation copper conductor Jelly Filled core wrapped polyester moisture Barrier Polyal screened Black Polythene Inner Sheath Black 03c Polythene outer sheathed under ground Armoured telephone cables <b>0.50mm</b> Make FINOLEX/ Polycab <b>10 PAIR JFA</b> ( Quoted rates are inclusive of laying & clamping charges, termination charges etc including all)	45	Meter		
4	Supply & installation ( including excavation / Horizontal direction drilling/boring without damage of surface road using Auger Machine ) of 50 Pair DP box powder coated lock & key arrangement 20 Gauge MS sheet Enough space provision for proper cable dressing with KRONE connector and SS Back mount fram MDF Box Local make Connector KRONE ( Quoted rates are inclusive of laying & clamping charges, termination charges etc including all)	1	No.		
5	Supply & installation of 20 Pair DP box powder coated lock & key arrangement 20 Gauge MS sheet Enough space provision for proper cable dressing with KRONE connector and SS Back mount frame MDF Box Local make Connector KRONE	1	No.		

6	Supply & Installation of 10 Pair DP box powder coated lock & key arrangement 20 Gauge MS sheet Enough space provision for proper cable dressing with KRONE connector and SS Back mount frame MDF Box Local make Connector KRONE	1	No.		
7	Supply & Installation of Thermo-shrinkable joining kits for making (a) Straight Through joint without transformer for 10. PIJF cables and where VF transformers are not required. All the materials required for the work are to be arranged by the contractor himself at his own cost. After jointing the cable through test such as insulation test, Continuity cable losses etc. to be carried out jointly with the. If any defect or any damage observed during jointing, the contractor should be redo the joint free of cost.	1	No.		
				<b>Total amount (Rs.)</b>	
				<b>Applicable taxes :</b>	
				<b>Grand Total Rs.</b>	

Amount in words \_\_\_\_\_

NID reserve the right to choose any one of the makes of materials and his decision is final & binding.