राष्ट्रीय डिज़ाइन संस्थान
NATIONAL INSTITUTE OF DESIGN
A Statutory Institute under DPIIT, Ministry of Commerce & Industry, Government of India
Paldi, Ahmedabad 380007. Tel: +91-79-26629500, +91-79-26629600
www.nid.edu

No. NID/NIQ/09/26-27 06.11.2026

## Notice Inviting Quotations (NIQ)

National Institute of Design (NID) invites quotations from reputed and experienced vendors for "Empanelment of contractors for Aluminium works to be carried out at NID Ahmedabad Campus and Gandhinagar Campus on an annual basis". (Including both labour and Material)

The quotations shall be received in the Office of the Chief Administrative Officer, NID, Paldi, Ahmedabad.

The last date of submission of sealed cover quotations: upto 5.00 pm on 30.11.2026

| | |
|---|---|
| Name of Work : | Empanelment of contractors for Aluminium works to be carried out at NID Ahmedabad Campus and Gandhinagar Campus on an annual basis. |
| Date & Time of opening of quotations: | 01.12.2026 at 11.00 am at NID Paldi, Ahmedabad |

Terms & conditions:

1. The bidder, having work experience of successfully completed similar works of at least Rs 8.00 Lakhs lakhs during the past 3 (Three) years as on 31.03.2026, is eligible for participation in this tender. Work experience with Govt institutions /offices shall be desirable though not essential. Purchase order/work order and Experience certificates of works done may be attached with submitted quotations. Aluminium works means Aluminium doors, windows, partitions with required glass, beading, mosquito nets etc.
2. The bidder is advised to visit the campus before submitting the quotation at his own cost and examine it and its surroundings to collect all information that he considers necessary for proper execution of the work. The bidder shall be deemed to have considered site conditions whether he has inspected it or not and to have satisfied himself in all respects before quoting his rates, and no claim or extra charges whatsoever in this regard shall be entertained / payable by the NID later. The work may be up to any height/floor of the building.
3. Empanelment contract time period shall be 12 months from the date of issue of work order, extendable by 12 months subject to satisfactory performance, mutual agreement on rates and continuation under the same terms and conditions.
4. The rates shall be inclusive of all applicable taxes. The quoted amount will be inclusive of all taxes, duties, other charges, etc.

5. Electricity will be provided by NID at one point free of cost. The Contractor shall also make standby arrangements for electricity to ensure uninterrupted supply, if required.
6. The rates shall be inclusive of material, labour, to & fro transportation, and applicable taxes. Part contract / conditional offer not acceptable.
7. The institute will analyse/compare the rates quoted by empanelled agencies on a work-to-work basis as per requirement of institute on time to time basis and award the contract to the lowest amongst the empanelled agencies during the period of empanelment. Decision of NID shall be final in award of the works.
8. The work order placed on the last day of the initial contract / extended period of contract shall also have to be honoured by the vendor.
9. In case of any mishap/incident related to the work in tender, the liability will be borne by the contractor only; NID will not be held responsible for any mishap in this regard, involving workers, buildings or materials etc. Accordingly, the contractor may take regarding workmen compensation policy etc. on his own interest.
10. The bidder shall be required to submit along with the Technical Bid envelope, Earnest Money Deposit (EMD) of Rs. 15000/- (Rupees Fifteen thousand) by Demand Draft / Banker's Cheque / Pay Order drawn on a Nationalized / Scheduled Bank payable at Ahmedabad in favour of the "National Institute of Design". EMD shall be refunded without interest to the unsuccessful Bidder after empanelment is finalised.
11. EMD of successful Bidders will be converted to Performance guarantee/ security deposit and shall be refunded without interest after successful completion of contract period. (Initial & Extension if any)
12. The payment shall be released against successful execution, final measurements as per actual area executed at site & submission of invoice duly checked, verified and certified for payment.
13. Retention amount: 10% of total contract value in addition to EMD/PG amount will be deducted from each bill amount, and it will be released without any interest after 90 days defect liability period.
14. Penalty for delay in completion: 0.5% (Point Five Percent) per week of the concerned contract value or part, subject to a maximum of five percent of the concerned contract value for delay in completion. For unsatisfactory work, 10% of the concerned contract RA/Final bill shall be deducted, without prejudice to other remedies available to NID, if not rectified as per NID satisfaction.
15. In case of items which the Contractor has to execute which are not covered in the tender, such non-tender item will be dealt with as extra item at market rate.
16. NID reserves the right to increase/decrease the quantities up to 30% as per requirement of NID till placement of work order.
17. NID reserves the right to reject any or all the Quotations, in part or full, without assigning reason thereof. Part or conditional offers are not acceptable.
18. In case of shortfall of document / insufficient information in bids, NID may ask for additional documents/information (only historic i.e. those pre-existing at the time of tender opening date) and bidder shall provide the same within the stipulated time.

19. Work shall be awarded to the technically qualified (as per Sr. no 1 above) lowest price bidder (as per Sr.No.7 above)
20. Please submit your offer in a sealed cover, addressed to the Chief Administrative Officer, National Institute of Design, Paldi, Ahmedabad 380007, up to the due date & time of submission.

Chief Administrative Officer
NID

Copy to: NID Website www.nid.edu

## Schedule of Quantity

**Name of work**: Empanelment of contractors for Annual Contract of Aluminium works to be carried out at NID Ahmedabad Campus and Gandhinagar Campus
**NIQ No.** NID/NIQ/09/26-27 dated 06.11.2026

| Item No. | Description of Item | Unit | Rate (Rs.) |
|---|---|---|---|
| **1** | Providing, Fabricating, Installing & Commissioning various types of Aluminium Glazing works, using original, certified JINDAL aluminium sections & profiles, including issue of fabrication drawings as per final designs, including taking all detailed measurements on site, including submission and approval of samples of sections & profiles intended to be used, including fabricating in workshop on machines as per manufacturer's specifications ( including all required and necessary hardware as per specifications including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required) , including transporting to site, proper storage and safe-keeping on site, including installation on site, including complete cleaning and commissioning of the finished product / article / assembly to the entire satisfaction of NID. The quoted rates will be on weight (per kg) basis as per acutal material used at site. The quoted rates will include 60 to 70 microns of Akzo Nobel / Jotun powder coating on all aluminium section, of approved shade & finish, with 25-years company warranty. The quoted rates shall include cost of all necessary hardware (unless otherwise specified) as per specifications & design approvals. Weight of such hardware will not be considered in the final measurements. Refer to separate list of approved brands / manufacturers. The quoted rates shall include fabrication of all glass components but excluding cost of supply of glass, compact sheet, pre-lam sheet, mosquito net, aluminium grill, or any other infill panels - as per design & specifications - which will be measured and billed separately. Alternative section and / or profiles, if required to be used in case of non-availability of specified JINDAL sections / profiles will be allowed only after prior approval of NID and the variation in weigh of such sections will not be more than 5% of JINDAL weights. All products, workmanships, assembly, fabrication, etc. will comply with applicable manufacturer's specifications and relevant BIS standards. | | |
| **1.1** | **Sliding Windows :**JINDAL 27 x 65 Domal Series<br>Including Section Numbers 21374, 21376, 21487, 21489, 21490, 21486, 19453 and all other related scetions in the series. | Kg | |

| | | | |
|---|---|---|---|
| **1.2** | **Sliding Windows :** JINDAL 29mm Gulf Series including Section Numbers G105951, G105954, G105953, G105955, G105956, G105957, G105949, G105945, G105946, G105947, G105948, G105952, and all other related scetions in the series | Kg | |
| **1.3** | **Casement (Openable) Windows, Door Shuttres & Fixed Glass :** JINDAL R40 Series including Section Numbers S5180, 21801, S5179, 19422, S5181, and all other related sections in the series | Kg | |
| **1.4** | **Fixed Partitions & Fixed Glass :** Using JINDAL Section Numbers 20062, 20063, 19352, 19360, and all other related sections in the series. | Kg | |
| **1.5** | **Openable Door Shutters :** Using JINDAL 85mm & 45mm Series including Section Numbers 19581, 19560, 19530, 19535, 19528, 19526, 19530, 19575, and all other sections in the series. | Kg | |
| **1.6** | **Any other section** : Any section from the JINDAL Catalogue including all requisite accessories and allied sections | Kg | |
| **2** | **Glass Works and other Infill Panels** | | |
| | Supplying Glass of approved make, thickness, type & finish for use in fabrication of aluminium glazing works, including submisison and approval of samples from NID, including taking details site measurements, including transport, storage & safe keeping ino workshop and on site. Item to be quoted for only supply of glass including insured transport, storage and safe keeping. The actual fabrication of glass to be included in scope as specified in separate item-A. Quoted rate to include cutting the glass, polishing of edges, etc. as required. Only the actual laid / visisble part of the glass will be measured and billed. Any wastage, breakage, etc. will not be considered, measured or billed. Recommended brands for glass: Saint Gobain, Asahi, ModiGuard/Guardian | | |
| 2.1 | Plain Clear Glass : 5 mm thick | Sqmt | |
| 2.2 | Plain Clear Glass : 6 mm thick | Sqmt | |
| 2.3 | Plain Clear Glass : 8 mm thick | Sqmt | |
| 2.4 | Plain Clear Glass : 10 mm thick | Sqmt | |
| 2.5 | Plain Clear Glass : 12 mm thick | Sqmt | |
| 2.6 | Toughened Clear Glass : 5 mm thick | Sqmt | |
| 2.7 | Toughened Clear Glass : 6 mm thick | Sqmt | |
| 2.8 | Toughened Clear Glass : 8 mm thick | Sqmt | |
| 2.9 | Toughened Clear Glass : 10 mm thick | Sqmt | |
| 2.10 | Toughened Clear Glass : 12 mm thick | Sqmt | |
| 2.11 | DGU (Double Glazed Unit) : 22 mm (5 mm + 12 mm + 5 mm) | Sqmt | |

| | | | |
|---|---|---|---|
| 2.12 | DGU (Double Glazed Unit) : 23 mm (5 mm + 12 mm + 6 mm) | Sqmt | |
| 2.13 | Laminated Glass (PVB:KURARAY TROSIFOL B500) : 13.52 mm (6 mm + 1.52 mm film + 6 mm) | Sqmt | |
| 2.14 | Sun Control Reflective Glass : 5 mm | Sqmt | |
| 2.15 | Other Infill Panels : 6mm Compact Sheet (Exterior Grade) | Sqmt | |
| 2.16 | Other Infill Panels : 12mm Pre-lam boards | Sqmt | |
| 2.17 | Other Infill Panels : SS 304 Zinc Coated 0.18 mm Mosquito Mesh | Sqmt | |
| 2.18 | Other Infill Panels :37mm x 37mm Aluminum Grill | Sqmt | |
| 3 | Removing and refixing of existing Aluminium & Glass partition with new HDPE rubber Gasket and all other necessary hardware fixtures, etc., complete as per direction of NID. | Sqmt | |
| 5 | Repairing of 12mm thick glass door (pivot and floor spring operated), including required fixtures as required. | Sqmt | |
| 7 | Removing and Re-fixing of new Floor Spring for Glass or Aluminium Doors with necessary fixtures. | | |
| 7.1 | - 80 Kg. Floor Spring | No. | |
| 7.2 | - 90 Kg. Floor Spring | No. | |
| 7.3 | - 120 Kg Floor Spring | No. | |
| 8 | Removing and Re-fixing of new Door Closer with 90° (degree) stop. for Aluminium Doors with necessary fixtures. | | |
| 8.1 | - 90 Kg. Door Closer | No. | |
| 8.2 | - 120 Kg. Door Closer | No. | |

Signature and Stamp

## Technical Specification

1. Aluminium section to be used: Jindal make as per tender items
2. Coating: Powder coating AkzoNobel / Jotun, 25-year warranty. 60 – 70 Micron
   Shade: Brown (selected)
3. Gasket: EPDM Gasket, considered AIGIRI / OSAKA / MPP make, with a 10-year warranty.
4. Glass: Saint-Gobain / HNG make considered, 6mm thick clear toughened
5. Compact Sheet: 6mm thick, ISI or equivalent make approved by NID, shade: Off white
6. Before proceeding with any fabrication work, the contractor shall prepare and submit complete fabrication and installation details/drawings for approval.
7. The measurement for payment shall be as per actual surface area at site, including frames, all fittings, beading, gasket, etc. as per tender items
8. Mosquito Net: S.S 304 Zinc Coated 0.18mm 18x18mm
9. Aluminium Grill: 37x37mm Aluminium Grill.
10. Floor Spring to be used: Enox, Ozone make.
11. Door Closer to be used: Enox, Ozone, Godrej, Dorma make